

15-16-16E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MESSMAN & RINEHART
Farm- Neill No. 1

SEC. 15 T. 16 R. 16E
SE SE NE

Total Depth. 1545'
Comm. 6-27-61 Comp. 7-3-61
Shot or Treated.
Contractor. Eureka Drlg.
Issued. 9-9-61

County Osage KANSAS



Elevation. 1025' RB

Production. Dry

CASING:
7" 106' cem w/30 sx.
4" 1545'

Figures Indicate Bottom of Formations.

lime & shale	50
lime	111
shale & shells	440
lime	465
shale	485
lime	517
shale	600
lime	641
shale w/lime strks	690
lime, sandy lime strks.	
black shale	769
lime & shale	775
shale	900
shale & shells	1085
shale	1290
sand & shale	1294
shale & sand	1380
shale	1463
Core #1	1483
Core #2	1508
lime	1537
lime	1545 RTD
Total Depth	

Core #1	1463 to 1480'	Burgess sand with oil
	1480 to 1483'	green shale, soft
Core #2	1483 to 1508'	dolomite w/chert & shale stks.
		all bleeding oil

DST #1 1380' weak blow, 15' mud.

TOPS: SCOUT	
Burgess	1461
Mississippi Chat	1470
Mississippi Lime	1519