

Bethel #3.

Driller: T.L. Russell, Garnett, Kans.

SW  $\frac{1}{4}$  NW  $\frac{1}{4}$  30-16-18

1036, 68.

February 10, 1927

(See other Bethel wells)  
in 325-165-17E

Franklin County

soil and clay	9	9	12 $\frac{1}{8}$ " pipe 20 ft.
lime blue hard	4	13	water 8BB per hr.
shale blue soft	27	40	
lime sandy hard	15	55	
shale white soft	65	120	
sand white soft	20	140	
shale dark soft	5	145	
sand white soft	50	195	water
shale light soft	15	210	
sand light soft	45	255	water
lime light hard	5	260	
sand light soft	18	278	
lime white hard	25	303	Eudora
shale dark soft	5	308	
lime light hard	8	316	
shale white soft	9	325	
lime white hard	19	344	Plattsburg
shale light soft	10	354	
sand	16	370	
shale light soft	2	372	Long-Banner Springs
shale light soft	108	480	10" casing 372
lime light hard	30	510	
shale light soft	12	522	
lime white hard	13	535	
shale blue soft	29	564	
lime light hard	16	580	
shale dark soft	12	592	
lime light hard	76	668	
shale light soft	sandy 67	735	
shale white soft	90	825	
lime light hard	12	837	
shale dark soft	5	842	
sand grey soft	22	864	water 1 bailer per hr.
shale light soft	6	870	
lime light hard	5	875	
shale light soft	10	885	
lime	6	891	
shale dark soft	8	899	
lime light hard	5	904	
shale dark soft	15	919	
lime light hard	3	922	
shale dark soft	8	930	
shale white soft	20	950	8" casing 944
shale light soft	95	1045	
shale dark soft	105	1150	show <u>oil</u>
sand dark	10	1160	
sandy shale light	52	1212	SIM casing 6 5/8"
sand gas	6	1218	
sand <u>oil</u>	17	1235	
sand	15	1250	
sand water	5	1255	Bottom hole SIM