

SIDE TWO

Operator Name Painter Oil Company Lease Name Lester Scott Well # 4Sec. 3 Twp. 16 Rge. 20 ☒ East ☐ West County Franklin

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken ☐ Yes ☒ No
 Samples Sent to Geological Survey ☐ Yes ☒ No
 Cores Taken ☒ Yes ☐ No

Formation Description
☒ Log ☐ Sample

Name	Top	Bottom
Shale	470'	520'
Sand Rainbow Bleed	520'	538'
Shale	538'	568'
Lime	568'	572'
Shale	572'	587'
Lime	587'	598'
Shale	598'	618'
Lime	618'	629'
Shale	629'	639'
Lime	639'	644'
Shale	644'	647'
Lime	647'	654'
Shale	654'	668'
Ft. Scott Lime Bleed	668'	674'
Shale	674'	698'
Sand Odor Bleed	698'	710'
Sandy Shale	710'	732'
Sand	732'	745'
Shale	745'	800'

CASING RECORD ☐ New ☐ Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface Completion	8" / 6 1/4"	6 1/2" / 2 7/8"		40' / 792'	Portland Cement	5 / 85	2% Bel

PERFORATION RECORD

Shots Per Foot	Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
2	698-708 First Sg.	40 SACKS SAND 65 BBL 60	698-708
2	727-737 Second Sg.	40 SACKS SAND 60 BBL 60	727-739

TUBING RECORD	Size	Set At	Packer at	Liner Run	☐ Yes ☐ No
---------------	------	--------	-----------	-----------	--

Date of First Production	Producing Method
4-12-88	☐ Flowing ☒ Pumping ☐ Gas Lift ☐ Other (explain).....

Estimated Production Per 24 Hours	Oil	Gas	Water	Gas-Oil Ratio	Gravity
	4 Bbls	50,000 MCF	0 Bbls	CFPB	24.9

METHOD OF COMPLETION

Production Interval

Disposition of gas: ☐ Vented ☒ Sold ☐ Used on Lease

☐ Open Hole ☒ Perforation ☐ Other (Specify)

☐ Dually Completed ☒ Conmingled

698-708
727-739

