

KERLYN OIL CO.
Reid No. 3.

SEC.17 T.16 R.20 E
NE SE NW ?
SE SE-1000

Total Depth. 707 $\frac{1}{2}$ '
Comm. 8-19-39 Comp. 8-30-39
Shot or Treated.
Contractor. S.R. McKinney
Issued. 5-15-43

County. Franklin



CASING:
8 $\frac{1}{4}$ " 13'
6 $\frac{1}{4}$ " 643'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

soil & clay	13	S 6 $\frac{1}{4}$ " anchor packer on string of 2" tubing set at
lime	35	696 to 700
shale dk	43	4' of perf. 2" tbg below packer at 700-704
lime	57	3 $\frac{1}{2}$ ' of 2" anchor below perforation to btm
shale	61	648' of 6 $\frac{1}{4}$ " csg (including threads) left in the
lime	78	well w/a 6 $\frac{1}{4}$ " x 2" stuffing box at the top,
shale	108	to confine gas 654-55
lime	140	
shale	206	
lime	229	
shale	248	
lime	254	
shale	281	
lime	296	
shale	299	
lime	302	
shale	317	
lime	345	
shale dk	353	
lime	378	
shale	381	
lime	396	
shale SIM @ 398	438	
sand oil show	440	
shale	511	
lime sdy	519	
shale gy	545	
lime	547	
shale limey	557	
shale green	564	
lime	574	
shale dk	591	
lime	602	
shale	616	
lime	619	
shale blk 6BW	624	
shale	627	
lime	629	
shale SIM @ 633	634	
lime	636	
shale	643	
lime	649	
shale SIM @ 650	654	
sand, gas, 40 M	655	
sand, oil show, no gas	656	
sand, oil show, no gas	657	
sand dry brkn	662	
shale limey	672	
shale	700	
sand, gas, 26 M	701	
sand, gas, 53 M	703	
sand, gas, 305 M	705	
sand, no gas, dry	707 $\frac{1}{2}$	
Total Depth.		