

D. D. Sandlin Drilling Co.

Rotary Drilling — Diamond Coring
Iola, Kansas, 66749

DRILLED FOR: CALDWELL & KIRK
JAN 19/75
WELL # 4
FARM STARIT
SEC 21 - 16 - 20
ANDERSON COUNTY, KANSAS.

THICKNESS	FORMATIONS	TOTAL DEPTH
5	soil & clay	5
9	clay & lime stone	14
51	lime hard	65
8	shale	73
5	hard sandy lime	78
10	shale w/ lime st	88
122	shale	210
25	lime (hard)	235
68	shale w/lime st	303
97	lime	400
5	shale	405
20	lime hard	425
157	shale	582
11	shale w/ lime shells	593
12	lime	605
65	shale	670
8	lime	678
11	shale	689
4	lime	693
24	shale	717
13	lime w/ shells	730
17	shale w/ lime st	747
7	lime sandy	755
3	shale	758
7	lime (hard)	765
23	shale w/ lime st	788
17	shale sandy (light odor)	805
20	sand broken	825
23	sandy shale (odor)	848
12	shale w/ shells	860 T.D.

Cored from 805' - 825'
drilled to 860' set 852' of 3" pipe
cemented to surface.