

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
UNION NATIONAL BANK BLDG., WICHITA, KANSAS

CASING RECORD

LOCATION < NW SW 400' NL 400' WL

SEC 35 T 16 R 20E.

20" 10"
15 1-2 8 1-4
12 1-2 6 5-8
5 3-16

FARM D. W. Brown NO. 1 COUNTY Franklin
COMPANY John L. Rich & J. A. Lloyd
CONTRACTOR C. E. Snyder.
COMMENCED COMPLETED Sept. 7, 1927.



TOTAL DEPTH 1057'

SHOT QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

ELEVATION 964.15
INITIAL PRODUCTION Dry.

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS 9/17/1927.

Formation	Depth
black soil	1
yellow clay	14
broken lime	16
lime	30
blue shale	40
lime	75
sandy shale	100
lime	125
shale light	200
lime	230
shale	250
lime	255
shale blue	285
lime	300
shale blue	320
lime	350
shale	358
lime	383
shale black (A little water)	388
lime	398
shale (Reduced from 10" to 8 1/4" at 409')	500
shale (A very little water)	559
lime	569
shale	610
lime	615
shale blue (A little water)	623
lime	626
shale white	637
lime	639
shale	645
sand	662
sand broken	668
shale light	680
shale gray	694
shale blue	699
lime	701
sand (Gas 3" water in 2" pipe)	716
shale drk	761
shale sandy	797
shale black	807
shale light	837
(Set 6 1/4" csg. at 816')	
shale	864
sand broken	872
shale dark	903
shale light	907
sand broken	915
shale dark	955
shale light	970
shale blue	980
shale black	1025
shale blue	1050
Mississippi lime	1057
Total Depth	1057'

Pulled & Plugged.