



7-16-21E

Custom  
oil & gas  
drilling  
Lease Development

310 N. Hospital Drive

Paola, Kansas 66071

(913) 294-9083

WELL LOG  
Deters - #5  
Seeker Oil, Inc.  
API No. 15-059-24,387  
October 31 - November 2, 1988

<u>Thickness of Strata</u>	<u>Formation</u>	<u>Total</u>
16	soil & clay	16
8	shale	24
5	lime	29
2	shale	31
17	lime	48
7	shale	55
12	lime	67
4	shale	71
23	lime	94
37	shale	131
17	lime	148
75	shale	223
25	lime	248
26	shale	274
6	lime	280
23	shale	303
4	lime	307
14	shale	321
2	lime	323
15	shale	338
25	lime	363
9	shale	372
23	lime	395
4	shale	399
18	lime	417 Hertha
117	shale	534
8	sand	542 Brown, good oil & gas show
39	shale	581
9	lime	590
7	shale	597
4	lime	601
7	shale	608
9	lime	617
13	shale	630
3	lime	633
16	shale	649

RECEIVED  
KANSAS OIL & GAS COMMISSION  
ASSOCIATION DIVISION  
Wichita, Kansas

7-16-21E

Deters - #5

3	lime	652
21	shale	673
1	lime	674
2	shale	676
1	sand	677 Brown, bleeding oil
1	brokensand	678 Thin sand & shale laminations
5	sand	683 Good sand, clean, bleeding oil
62	shale	745 TD

Set 23.40' of 6 $\frac{1}{2}$ " surface casing.  
Set 732.0' of 2 7/8" 8 Round upset pipe.  
Seating nipple set at 612.80'.

UPPER SQUIRRELL CORE TIMES

	<u>MIN.</u>	<u>SEC.</u>
678		50
679	1	10
680	1	00
681	1	00
682	1	05
683	1	15
684	1	15
685	1	10
686	1	15
687	1	10
688	1	15
689	1	20
690	1	15