

**IMPORTANT**  
 Kans. Geo. Survey request  
 samples on this well.

**KANSAS DRILLERS LOG**

State Geological Survey  
 WICHITA BRANCH  
 S. 4 T. 18 R. 21 E  
 Loc. SE SE

API No. 15 — 059 — 21,173  
 County Number

County Franklin

640 Acres  
 N

Operator  
Elton R. Greer

Address  
Route 1, Box 219-B Wellsville, Ks. 66092


Well No. #30 Lease Name Lidikay

Footage Location 330 495 WEL 495 NSL  
 feet from (N) (S) line feet from (E) (W) line

Principal Contractor E. R. Greer Geologist E. R. Greer

Spud Date 6-8-80 Total Depth 710 P.B.T.D. 703

Date Completed 6-9-80 Oil Purchaser La Jet Inc.



Locate well correctly

Elev.: Gr. \_\_\_\_\_

DF \_\_\_\_\_ KB \_\_\_\_\_

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	7 1/2	6 1/4	20	26	Portland	3	
Production	5 1/4	2 3/8	4.7	710	Portland	(Circulated)	

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	1/2 jet	678-694

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
30 sacks sand/ 100 bbl water	678-694

**INITIAL PRODUCTION**

Date of first production	<u>7-20-80</u>	Producing method (flowing, pumping, gas lift, etc.)	<u>pumping</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>1 bbl</u> bbls.	Gas _____ MCF	Water <u>1 bbl</u> bbls. Gas-oil ratio _____ CFPB
Disposition of gas (vented, used on lease or sold)		Producing interval (s)	

**INSTRUCTIONS:** As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **Elton R. Greer** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. **30** Lease Name **Lidikay** oil

S 4 T 16 R 21 E

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil & clay	0	12		
lime	12	16		
shale	16	23		
lime	23	33		
shale	33	39		
lime	39	59		
shale	59	97		
lime	97	117		
shale	117	189		
lime	189	215		
shale	215	238		
lime	238	244		
shale	244	304		
lime	304	329		
shale	329	333		
lime	333	359		
shale	359	363		
lime	363	375	Base of Hertha	
shale	375	535		
lime	535	542		
shale with lime streaks	542	587		
lime	587	595		
shale	595	608		
lime	608	612		
shale	612	614		
lime	614	646		
shale	646	649		
lime	649	656	Base Ft. Scott	
shale	656	665		
brown sandstone	665	698	(oil sand)	
shale	698	710	T. D.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*Elton R. Greer*  
Signature

*Owner*  
Title

*12-15-80*  
Date

REPRODUCTION OF THIS WELL LOG  
FOR USE IN OTHER LOGS  
IS PROHIBITED