


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

A.D. HOSTETTER ET AL.
Anne H. Gross No. 3.

SEC. 8 T. 16 R. 21E.
NE SE SE SE
50' fr E 400' fr S.L. SE $\frac{1}{4}$

Total Depth. 850
Comm. 6-12-37 Comp. 6-27-37
Shot or Treated. 30 qts 665-642
Contractor. J.W. Lemons & Sons.
Issued. 10-21-39

County Franklin.



CASING.

8 $\frac{1}{4}$ " 11 $\frac{1}{2}$ "
6 $\frac{1}{4}$ " 630 $\frac{1}{2}$ "

Elevation.

Production. 10 B.?

Figures Indicate Bottom of Formations.

soil	8	sand hard	656
limo	19	sand soft	660
shalo dark	26	broken sand	665
limo	60	shalo grey	670
shalo	101	shalo grey	675
limo	124	shalo	700
shalo sdy	190	red rock	705
limo hard	213	shalo sdy	738
shalo grey	237	sand gas & wtr	793
limo	245	shalo water	795
shalo grey	269	sand & water	850
limo	274		
shalo	283	Total Depth.	
limo	285		
shalo grey	300		
limo	324		
shale blk	331 6 BW		
limo	353 BFW	shot from 665-642 with 30 qts.	
shalo blk	358 SLM 365	and saved for oil producer.	
limo hard	369		
shalo grey	371		
limo	373		
shalo light	385		
shalo grey	405		
sdv limo	420		
shalo grey	475		
sdv shale oil show	482		
shale grey	505		
limo sholls	510		
shalo light	515		
limo	525		
shalo white	533		
sdv lime Oil show	550		
shalo sdu wh	560		
shalo grey	569		
limo	574		
shalo grey	589		
limo	599		
shalo blk wtr big.	595		
limo	605		
shalo grey	610		
limo	612		
shalo dark	622		
limo	625		
shalo	631		
sand light soft	654 light show oil		


8-16-21E

Form PO-214 Sheet 2 1-37 15M

LOG OF WELL

SHEET No. 1

District North Kans. Owner ^{A.D.} Hostetter et al Farm Anne H. Cross Well No. 3

FORMATION	BOTTOM	AMOUNT	COLOR	HARD or SOFT	DEPTH CORES TAKEN	REMARKS
Location App; N2 SE4 & E 20 Acres of S2 SE4 Sec. 8 - T 16 R 21 Franklin Co. Commenced drilling 6-12-37; Completed drilling 6-27-37. J. W. Lemons & Sons, Paola, Kans. Drilling contractor. Day Driller Carl Moore; Tool Dresser Walter Carpenter. → 300' from So. & 50' from E. lines of SE. 4.						
Soil	8	8				
Lime	19	11				
Shale	26	7 ⁿ	Dark			
Lime	60	34				
Shale	101	41				
Lime	124	23				
Shale, Sdy	190	66				
Lime	213	23		hard		
Shale	237	24	gray			
Lime	245	8				
Shale	269	24	gray			
Lime	274	5				
Shale	283	9				
Lime	285	2				
Shale	300	15	gray			
Lime	324	24				
Shale	331	7	black			
Lime	353	22				
Shale	358	5	black			
Lime	369	11		hard		
Shale	371	2	gray			Water 6 Bls. BFW SIM 365'
Lime	373	2				
Shale	385	12	light			
Shale	405	20	gray			
Sandy Lime	420	15				
Shale	475	55	gray			
Sandy Shale	482	7				
Shale	505	23	gray			
Lime shells	510	5				
Shale	515	5	light			
Lime	525	10				Oil show
Shale	533	8	white			
Sandy Lime	550	17				
Shale, sandy	560	10	white			
Shale	569	9	gray			
Lime	574	5				
Shale	589	15	gray			
Lime	593	4				
Shale	595	2	black			
Shale	599	4	light			
Lime	605	6				Black water - big
Shale	610	5	gray			
Lime	612	2				
Shale	622	10	dark			
Lime	625	3				
Shale	631	6				
Sand	654	23	light	soft		
Sand	656	2		hard		
Sand	660	4		soft		
Broken sand	665	5				
Shale	670	5	gray			light oil show
Shale	675	5	gray			
Shale	700	25				
Shale	705	5				
Shale, sandy	738	33				

8-16-21E

Form PO-214 Sheet 2 1-37 15M

LOG OF WELL

SHEET No. 2

District North Kans. Owner A.D. Hostetter et al Farm Anne H. Cross Well No. 3

FORMATION	BOTTOM	AMOUNT	COLOR	HARD or SOFT	DEPTH CORES TAKEN	REMARKS
Sand	793	795	55			Gas & water
Shale		795	2			
Sand & water		850	55			Water
Shot from 665-642 with 30 qts. SNG and saved for oil producer.						
CASING RECORD:						
8-1/4" 17# Casing			11-1/2'			
6-1/4" 13# "			630-1/2'			