


KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 059 — 21,463
County NumberState Geological Survey
Wichita Branch
T. 16 R. 21 E
Loc. NE/4 SW/4

County Franklin

640 Acres
N

Locate well correctly

Elev.: Gr. _____

DF _____ KB _____

Operator

E. D. Mauslein

Address

Route # 1, Wellsville, Ks. 66092

Well No.

2-A

Lease Name

Mauslein Fee

Footage Location

900 EWL

450 SNL

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

E. R. Greer

Geologist

E. R. Greer

Spud Date

9-24-80

Date Completed

9-26-80

Total Depth

764

P.B.T.D.

713

Directional Deviation

Oil and/or Gas Purchaser

La Jet Inc.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	7 1/2	6 1/4	30	25	Portland	3	
Production	5 1/4	2 3/8	4.7	760	Portland	(circulated)	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	1/2 jet	652-682
TUBING RECORD					
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
50 sacks sand / 100 bbl water	652-682

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
11-1-80		pumping			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		7		10	
		bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)				Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

E. D. Mauslein

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

2-A

Lease Name

Mauslein Fee

Oil

S 9 T 16 R 21 E

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil & clay	0	16		
lime	16	30		
shale	30	38		
lime	38	69		
shale	69	112		
lime	112	134		
shale	134	205		
lime	205	226		
shale	226	253		
lime	253	260		
shale	260	316		
lime	316	338		
shale	338	344		
lime	344	338		
shale	338	346		
lime	346	368		
shale	368	374		
lime	374	384	Base of Hertha	
shale	384	535		
lime	535	540		
shale	540	588		
lime	588	595		
shale	595	609		
lime	609	612		
shale	612	615		
lime	615	632		
shale	632	643		
lime	643	647	Base of Ft Scott	
shale	647	656		
brown sandstone	656	707	(oil sand)	
shale	707	764	Total Depth.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

E. R. Mauslein

Signature

Geologist

Title

12-15-80

Date