

WICHITA BRANCH
KANSAS DRILLERS LOGAPI No. 15 — 121 — 21139
County Number

Operator

Reese Exploration, Inc.

Address

PO Box 11598, KCMO 64138

Well No.

12-79

Lease Name

Mitchell

Footage Location

1720

feet from ~~XX~~ (S) line

4360 FSL 1480 FWL-KCC

480

feet from ~~XX~~ (W) line

Principal Contractor

Michael Drilling

Geologist

Spud Date

Nov. 1979

Total Depth

693

P.B.T.D.

Date Completed

Dec. 1979

Oil Purchaser


LaJet, Inc.

S. 12 T. 16 R. 21 E
WLoc. NW $\frac{1}{2}$

County Miami

640 Acres

N



Locate well correctly

Elev.: Gr.

DF

KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8-7/8	6-1/4	17#	40	Portland	4	none
2"	5-1/4	2-3/8	4#	672	"	90	2% Gel

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
none		

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at
none		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Frac Hot Oil 96 sacks sand	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
Dec. 1979	Pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	1 bbls.	0 MCF		bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Reese Exploration, Inc.

12-16-21E

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Oil

Well No.

12-79

Lease Name

Mitchell

S 12 T 16 R 21 ^E
Wk

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil and clay	0	11		
lime	11	27		
shale	27	32		
lime	32	69		
shale	69	97		
lime	97	114		
shale	114	199		
lime	199	220		
shale	220	251		
lime	251	256		
shale	256	314		
lime	314	338		
shale	338	346		
lime	346	369		
shale	369	373		
lime	373	387		
shale	387	555		
lime	555	561		
shale	561	592		
lime	592	598		
shale	598	615		
lime	615	619		
shale	619	623		
lime	623	638		
lime shale	638	642		
shale	642	656		
lime	656	663		
shale	663	674		
sand	674	679		
shale	679	693		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Bookkeeper

Title

2-4-80

Date