

WICHITA BRANCH
KANSAS DRILLERS LOGAPI No. 15 — 121 — 21140
County Number

Operator

Reese Exploration, Inc.

Address

PO Box 11598, KCMO 64138

Well No.

13-79

Lease Name

Mitchell

Footage Location

2160 feet from (N) (S) line 480 feet from (E) (W) line

Principal Contractor

Michael Drilling

Geologist

Spud Date

Nov. 1979

Total Depth

750

P.B.T.D.

Date Completed

Dec. 1979

Oil Purchaser

LaJet, Inc.


S. 12 T. 16 R. 21 E

Loc. NW 1/4

County Miami

640 Acres

N



Locate well correctly

Elev.: Gr.

DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8-7/8	6-1/4	17#	40	Portland	4	none
2"	5-1/4	2-3/8	4#	737	"	90	2% Gel

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
none					

PERFORATION RECORD

TUBING RECORD

Size	Setting depth	Packer set at			
none					

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Frac - Hot Oil 92 sacks sand	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
Dec. 1979		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	1	0			
	bbls.	MCF		bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Reese Exploration, Inc.

12-16-21E

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Oil

Well No.

13-79

Lease Name

Mitchell

S 12 T 16 R 21 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil and clay	0	11		
lime	11	31		
shale	31	37		
lime	37	50		
shale	50	55		
lime	55	74		
shale	74	102		
lime	102	118		
shale	118	203		
lime	203	224		
shale	224	255		
lime	255	260		
shale	260	318		
lime	318	344		
shale	344	351		
lime	351	374		
shale	374	378		
lime	378	391		
shale	391	561		
lime	561	567		
shale	567	597		
lime	597	601		
shale	601	617		
lime	617	620		
shale	620	626		
lime	626	645		
shale	645	666		
lime	666	668		
shale	668	679		
sand	679	682		
shale	682	750		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Bookkeeper

Title

2-4-80

Date