

State Geological Survey

WICHITA BRANCH

KANSAS DRILLERS LOG

API No. 15 — 059 — 20,404
County Number

Operator

Rader Oil Co.

Address

R. R. #1 Eudora, Kansas 66025

Well No.

#5

Lease Name

Chambers

Footage Location

665 655 FSL 1984 FEL 1,900
feet from (M) (S) line feet from (E) (W) line

Principal Contractor

Kent Drilling Co.

Geologist

Dick Rader

Spud Date

Sept. 16, 1977

Total Depth

742

P.B.T.D.

Date Completed

Nov. 26, 1977

Oil Purchaser

Bluebird Oil Co.


S. 19 T. 16 R. 21 E W

Loc. NE SW SE SW SW SE

County Franklin

640 Acres

N



Locate well correctly

Elev.: Gr. _____

DF _____ KB _____

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	10	7	24	35	common	9	
Production	6 $\frac{1}{4}$	4 $\frac{1}{2}$	10.50	729	Pozmix	100	salt, gel pozmix

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	$\frac{1}{2}$ jet	708-713
TUBING RECORD					
Size	Setting depth	Packer set at			
2"	705				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
45 Sx. Sand 120 B. O.	708-713

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
		Pumping			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
5		bbls.	MCF	2	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
			708-713		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Rader Oil Co.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil
Well No. 5	Lease Name Chambers	
S 19 T 16 R 21 E		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil & Clay	0	10		
Lime	10	24		
Shale	24	30		
Lime	30	63		
Shale	63	101		
Lime	101	117		
Shale	117	198		
Lime	198	220		
Shale	220	247		
Lime	247	252		
Shale	252	282		
Lime	282	294		
Shale	294	314		
Lime	314	342		
Shale	342	350		
Lime	350	370		
Shale	370	373		
Lime	373	390		
Shale	390	548		
Lime	548	560		
Shale	560	567		
Lime	567	576		
Shale & Shells	576	707		
Sand	707	713	Squirrel	707-713
Shale	713	742 TD		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature <i>D. P. Rader</i>
	Owner
	Title
	Date Dec. 12, 1977