

State Geological Survey
WICHITA, BRANCH

KANSAS DRILLERS LOG

API No. 15 — 121 — 20,234
County Number

S. 24 T. 16 R. 21 E W
Loc. 660 FEL 660 FNL SE
County Miami NG SE SG
640 Acres N
1600

Operator
Reese Enterprises, Inc.

Address Box 11598 Kansas City, Missouri 64138


Well No. #8 Lease Name Cayot

Footage Location 1000 FSL & 660 FEL-KCC
660 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor Kent Drilling Co. Geologist

Spud Date August 25, 1974 Total Depth 720' P.B.T.D. 696'

Date Completed August 29, 1974 Oil Purchaser Bluebird Oil Co.



Elev.: Gr. _____
DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Production	6 1/2	4 1/2	9.5	720'	Bulk	105	2 sacks Jell 4 sacks Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
0		7	1	Glass 10	668' to 680'

Size	Setting depth	Packer set at			
2"	668'	None			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
50 gal. 15% Acid, 30 sx. sand with 105 bbl. oil	668 to 680

INITIAL PRODUCTION

Date of first production Sept. 3, 1974 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS Oil 10 bbls. Gas 0 MCF Water 0 bbls. Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Vented Producing interval (s) 668 to 680

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Reese Enterprises Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

8

Lease Name

Cayot

Oil

S24 T16 R21 E W

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil & Clay	6	680'	Squirt	684.4
Lime	13	19		
Shale	5	24		
Lime	10	34		
Shale	10	44		
Lime	20	64		
Shale	25	89		
Lime	15	104		
Shale	91	195		
Lime	19	214		
Shale	34	248		
Lime	5	253		
Shale	31	284		
Lime	11	295		
Shale	19	314		
Lime	26	340		
Shale	8	348		
Lime	21	369		
Shale	3	372		
Lime	13	385		
Shale	168	530		
Lime	30	560		
Shale	29	589		
Lime	8	597		
Shale	16	613		
Lime	4	617		
Blk. Shale	6	623		
Lime	3	626		
Shale	4	630		
Br. Lime	31	661		
Shale	5	666		
Oil Sand	16	682		
Sandy Shale	4	686		
Shale	14	700 T.D.		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Signature

Jack W. Sanders
Production Supt.

Title

Dec. 30, 1974

Date