

24-16-21E

SUTCLIFFE PIPE & SUPPLY

ICE BELT

ORIGINAL

Well Record

PHONE HE... CHANUTE
... WICHITA

6. CRANT. CHANUTE KANSAS
5705 N. BROADWAY, WICHITA, KANSAS

COMPLETE LINE OF NEW & USED PIPE • BELTING • STORAGE TANKS • WIRE LINES

Well No. Farm Phillips Producer, Roger F. Phillips

Location Sec. 24 Twp. 16 S Rg. 21 E

Elevation State Kansas County Miami

Kind (Oil, Gas, Water, Dry Hole) Water Supply Contractor Sutcliffe Pipe & Supply

Producing formation Top Bottom

Shot with qts. from to

Packer set at Kind Blah

Liner from to Perforated from to

LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
2	Soil	2	3	Lime	635
10	Clay	12	10	Shale	645
2	Lime	14	3	Lime	648
3	Shale (Little water)	17	14	Shale	662
6	Lime	23	4	Shale	668
4	Shale	27	7	Sand-show of oil	675
8	Lime	45	25	Sandy shale	700
3	Shale	48	65	Shale	765
2	Lime	65	2	Lime	767
5	Shale	90	1	B. Shale	771
7	Lime	107	16	L. Shale	787
8	Shale	195	5	Red Bed	792
10	Lime	215	133	Shale	925
5	L. Shale	250	25	Shale Sandy	950
5	Lime	255	35	Sand-water	985
5	L. Shale	270	9	D. Sandy Shale	994
3	Lime	273	28	Sand	1022
2	Sandy Shale	285	20	Slate	1042
8	Lime	293	73	Lime	1115
2	Shale	315	10	Sandy Lime water	1125
4	Lime	390			
0	Shale	550	5	Lime - dead oil	1130
7	Lime	557			
2	Shale	585			
6	Lime	591			
5	Shale	616			
5	Lime - show oil	621			
5	Slate water	626			
4	Lime	630			
2	Shale	632			

Total Depth 1130'

Open Hole

Casing 8" at 662'

Casing at

Casing at

Cement 90 sacks cement

Tubing

Rods

Additional Information

3 E.W.P.H. @ 215

8 E.W.P.H. @ 374

SIM 616

(Corrected measurement from 925 to

SIM 897)

Gas At 906

SIM 1045 1/2

Running 1052' of 7" and pulling 655' of

8" and cementing 7"

Testing water fillup filled up 120' in

one hour.

Water fillup 300' in one hour.

Date Completed September 1, 1962

O. K.

Superintendent

Started Aug. 12, 1962

697

611