

S. SUTCLIFFE PIPE & SUPPLY

JOE SUTCLIFFE

Well Record

110 S. GRANT, CHANUTE KANSAS

5705 N. BROADWAY, WICHITA, KANSAS

24-16-21E
ORIGINAL

WE HE 1-1940 CHANUTE
E. Temple 8-3601 WICHITA

COMPLETE LINE OF NEW & USED PIPE - BELTING - STORAGE TANKS - WIRE LINES

Well No. 10 Farm Phillips Producer Roger F. Williams
Location Sec. 24 Twp. 16 S Rg. 21 E
Elevation State Kansas County Miami
Kind (Oil, Gas, Water, Dry Hole) Contractor Sutcliffe Pipe & Supply
Producing formation Top Bottom
Shot with 20 qts. from to
Packer set at Kind Size
from to Perforated from to

LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
6	Soil & clay	8	3	Lime	613
8	Lime	16	7	Slate	620
4	Shale	20	3	Lime	623
15	Lime	35	4	Shale	627
5	Shale	40	3	Lime	630
20	Lime	60	27	Shale	657
4	L. shale	64	2	Lime	659
5	Red bed	69	7	Shale	666
19	L. shale	88	1	Sand - odor	667
17	Lime	105	1'3"	Sandy shale	668'3"
85	L. shale	190	1'2"	Shale - 1'10" of	670.
20	Lime	210			670.
38	Shale	248	1'3"	Sand & lime	669'6"
3	Lime	251	1'	Sand-lime on top	670.9
19	Shale	270	4.2	Sand oil	674.7
20	Lime	290	4.0	Sand & brk sd.	678.7
3	Shale	293	1.3	Shale	680.
5	Lime	298	2.4	Shale & brk sd	682.4
17	Shale	315			
8	Lime	323			
3	Shale	326			
14	Lime	340			
5	D. shale	345			
24	Lime	369			
2	Slate	371			
15	Lime	386			
166	Shale	552			
10	Lime	562			
25	Shale	587			
8	Lime	595			
15	Shale	610			

Total Depth 682.5
Open Hole
Casing 8" at 11' 11"
Casing 7" at 635' 6"
Casing 4" at 669'
Cement 160 sacks
Tubing
Rods
Additional Information
Cored 669.3 - 682.5
Sand to 678.7
Brk sd & shale 682.5
Run SL 682.5
14 sacks Gel
Pump plug to 625'
Plug back to 669' w/rock
Pull 7" pipe & cement

Completed March 23, 1962

O. K.

Superintendent

Started March 15, 1962