

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 121 — 21,391
County Number

Operator

Scimitar Resources Ltd.

Address

P. O. Box #211 Paola, Kansas 66071

Well No.

#S-2A

Lease Name

Pflug

Footage Location

160

feet from (N) line

3730 FSL 3419 FEL-KCC

760

feet from (E) line

Principal Contractor

McGown Drilling, Inc.

Geologist

Jim Stegeman

Spud Date

3-17-80

Date Completed

3-18-80

Total Depth

730'

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

Producers Group

S. 25 T. 16 R. 21 E W


Loc. 760' WEL & 160' SNL S2 NW

County Miami

NW SE NW

640 Acres
N

KCC



Elev.: Gr. _____

DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
		2 1/2"	5.82	722'	Portland A	166	3.5 sks of gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
170 bbl. water with clay stablizer	672-682'
150 lbs. rock salt 8000 lbs. sand	
10 gallons LS3 (CCA)	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
5-9-80		pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	2.7		2.5		
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
vented			squirrel		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No.	Lease Name	
S <u>25</u> T <u>16</u> R <u>21</u> ^E _{NE}		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil/Clay	0	49		
Lime	49	64		
Shale	64	96		
Lime	96	109		
Shale	109	201		
Lime	201	221		
Shale	221	248		
Lime	248	257		
Shale	257	282		
Lime	282	295		
Shale	295	312		
Lime	312	338		
Shale	338	352		
Lime	352	371		
Shale	371	375		
Lime	375	382		
Shale	382	383		
Lime	383	387		
Shale	387	559		
Lime	559	568		
Shale	568	596		
Lime	596	602		
Shale	602	681		
Lime	618	677		
Core	677	691		
Oil Sand	691	694		
Sand & Shale	694	701		
Shale	701	730/TD		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature Title Date
---------------	--

15-121-21,391
25-16-21E

Well No.	2	Farm	Pflug	Producer	Scimitar Resources, Ltd.
Location	S $\frac{1}{2}$ of NW $\frac{1}{4}$			Sec	25
				Twp.	16
				Rg.	21 E
Elevation				State	Kansas
				County	Miami
Kind (Oil, Gas, Water, Dry Hole)	Oil			Contractor	McGown Drilling, Inc.
Producing formation				Top	Bottom
Shot with	qts.			from	to
Packer Set at				Kind	Size
Liner	from			to	Perforated from
					to

[illegible]

Total Depth 730'

Open Hole

Casing 2 $\frac{1}{2}$ " at 722'

Casing at

Casing at

Cement

Tubing

Rods

Additional Information

SN 672

Date Completed 031880

O. K.

Superintendent