

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 121 — 21441
County NumberS. 25 T. 16 R. 21 E
Loc. 160 SNL 1160 WEL NW 1/4
Miami SW SG NW
County
640 Acres
N
KCC

Operator

Scimitar Resources Ltd.

Address

P.O. Box 211 Paola, Kansas 66071

Well No.

S-7A

Lease Name

Pflug

Footage Location

160

2761 FSL ! 3795 FEL-KCC
feet from (N) line feet from (E) line

Principal Contractor

McGown Drilling, Inc.

Geologist

Jim Stegeman

Spud Date

3/24/80

Date Completed

3/26/80

Total Depth


711'

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

Producers Group



Locate well correctly

Elev.: Gr.

DF

KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Production	6 1/8	2 1/2	5.82	696'	Portland A	138	gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2 per 5 total	2 1/8" glass jets	650-652'
			3 per 35 total	2 1/8" glass jets	654-666'

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
8000# 20/40 frac sand	650-666'
300# rock salt	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
6/12/80		pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	2.7	bbls.	MCF	2.5	bbls.
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
Vented			Squirrel		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

25-16-21E

Well No.	S-7-A	Farm	Pflug	Producer	Scimitar Resources, Ltd.		
Location	SE of NW 1/4			Sec.	25	Twp.	16 Rg. 21 E
Elevation				State	Kansas	County	Miami
Kind (Oil, Gas, Water, Dry Hole)	Oil			Contractor	McGown Drilling, Inc.		
Producing formation				Top	Bottom		
Shot with	qts.			from	to		
Packer Set at				Kind	Size		
Liner	from			to	Perforated from	to	

LOG					
Top			Bottom		
Thick- ness	Strata	Depth	Thick- ness	Strata	Depth
	Soil/clay	0	72		
	Lime	72	86		
	Shale	86	176		
	Lime	176	196		
	Shale	196	226		
	Lime	226	234		
	Shale	234	256		
	Lime	256	269		
	Shale	269	290		
	Lime	290	316		
	Shale	316	326		
	Lime	326	348		
	Shale	348	358		
	Lime	358	364		
	Shale	364	531		
	Lime	531	538		
	Shale	538	546		
	Lime	546	547		
	Shale	547	571		
	Lime	571	579		
	Shale	579	593		
	Lime	593	598		
	Shale	598	628		
	Lime	628	633		
	Shale	633	651		
	Core	651	669		
	Sand & Shale	651	655		
	Sand	655	662		
	Shale	662	711/TD		

Total Depth 711'

Open Hole

Casing $2\frac{1}{2}$ " at 696'

Casing at

Casing at

Cement

Tubing

Rods

Additional Information

SN 6461

Date Completed 032680

O. K.

Superintendent