

15-059-20544


State Geological Survey
KANSAS DRILLERS LOG
WICHITA BRANCH

S. 29 T. 16 R. 21 E
W

Loc. NE SW NE

County Franklin

640 Acres
N



Elev.: Gr.

DF KB

API No. 15 — 059 — 20,546
County Number

Operator
Rader Oil Company

Address
R. R. #1 Eudora, Kansas 66025

Well No. #4 Lease Name Stevenson

Footage Location
1,540 feet from (N) line 1,584 feet from (E) line

Principal Contractor Kent Drilling Co. Geologist Dick Rader

Spud Date July 18, 1978 Total Depth 643 P.B.T.D.

Date Completed August 7, 1978 Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	10	7	24	30	common	7	
Production	6 1/4	4.5	10.5	597	Pozmix	90	Salt, poz. gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	1/2 Jet	576-581
TUBING RECORD					
Size	Setting depth	Packer set at			
2	573				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
45 SX. sand, 90 BO	576-581

INITIAL PRODUCTION

Date of first production August 8, 1978	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS Oil 5 bbls. Gas 0 MCF Water 0 bbls. Gas-oil ratio CFPB	Producing interval (s) 576-581

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Rader Oil Co.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil
Well No. 4	Lease Name Stevenson	
S <u>29</u> T <u>16</u> R <u>21</u> E <u>W</u>		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil & Clay	0	17		
Lime	17	37		
Shale	37	123		
Lime	123	146		
Shale	146	169		
Lime	169	175		
Shale	175	200		
Lime	200	215		
Shale	215	237		
Lime	237	260		
Shale	260	272		
Lime	272	283		
Shale	283	286		
Lime	286	306		
Shale	306	451		
Lime	451	461		
Shale	461	508		
Lime	508	514		
Shale	514	530		
Lime	530	533		
Shale	533	543		
Lime	543	546		
Shale	546	554		
Lime	554	557		
Shale	557	564		
Lime	564	566		
Shale	566	572		
Sand	572	596	Squirrel	572-596
Shale	596	618		
Lime	618	620		
Shale	620	643 TD		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 _____ Signature Owner _____ Title September 1, 1978 _____ Date
---------------	--