

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGState Geological Survey
WICHITA, BRANCHAPI No. 15 — 121 — 23,591
County Number

Operator

B & B Energy

Address

404 Persimmon Dr.

Well No.

B1

Lease Name

Compton

Footage Location

2590

feet from (N) line

50

feet from (E) line

Principal Contractor

Larry Bogle

Geologist

none

Spud Date

11-17-81

Date Completed

12-20-81

Total Depth

765

P.B.T.D.

Directional Deviation


Oil and/or Gas Purchaser

LaJet Inc.

S. 36 T. 16 R. 21 E

Loc. 2590 ESL, 50' FEL

County Miami

640 Acres
N

Elev.: Gr.

DF

KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	8 5/8"	6 1/4"	141bs	50'	portland	5	none
production	5 1/4"	2 3/8"	3.75	736'	portland	97	5 sacks gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2.2/ft.	1 11/16 G.J.	690-696 704-710
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
150 Bbls. gel water	690-696
30 sacks sand	704-710

INITIAL PRODUCTION

Date of first production 12-23-81		Producing method (flowing, pumping, gas lift, etc.) pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil one bbls.	Gas none MCF	Water 15 bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold) vented			Producing interval(s) 690-696 704-710		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator B & B ENERGY		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. B-1	Lease Name COMPTON	OIL
S <u>26</u> T <u>16</u> R <u>21</u> ^E _W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil				2
clay				4
shelf rock				15
lime				22
shale				42
lime				55
shale				80
lime				97
shale				200
lime				237
shale				283
lime				285
shale				331
lime				380
shale				553
lime				580
shale				
oil sand	692	712	squirrel	712
dark shale				765

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>David P. Bentley</i>
	Signature
	Partner in B & B Energy
	Title
	2-23-82
	Date