

Company

18-16-25E

Sec. 10 T. 10 R. 23

Farm Collins

No. 1

Loc. From South - 535 ft.

From East - 375 ft.

Total Depth 631

Comm. Nov. 6/36

Comp.


Shot or Treated

Contractor Sands et al

Issued

County Miami

Plotted



Casing

20 in.

10 in.

15 1/2

8 1/4

12 1/2

6 5/8

13 3/8

5 3/16

Elevation

Production

Figures Indicate Bottom of Formation

Thickness of Strata	Kind of Rock	Total Depth	Remarks
15	Clay	15	
13	Boulders	28	
47	Shale	75	
10	Limestone	85	
3	Shale	88	
10	Sand	98	
24	Shale	122	
6	Limestone	128	
43	Shale	171	
10	Limestone	181	Drum
13	Dk. Shale	194	
22	Limestone	216	Winterset
4	Dk. shale	220	
2	Limestone	222	
3	Dk. Shale	225	
46	Limestone	271	Bethany Falls & Hertha
26	Shale	297	
5	Sand	302	Gas
8	Sand	310	Oil
167	Shale	477	
4	Limestone	481	Altamont
15	Shale	496	
10	Limestone	506	Sandy
5	Sand	511	Gas
16	Dk. Shale	527	S.L.M.
4	Bk. Shale	535	Gas
3	Sand	538	
6	Shale	544	Sandy
8	Limestone	552	
20	Shale	572	
4	Limestone	576	
2	Shale	578	
3	Bk. Shale	581	
4	Shale	585	
6	Limestone	591	
5	Shale	596	
4	Limestone	600	
2	Shale	602	
6	Bk. Shale	608	Gas
12	Shale	620	
9	Sand	629	
2	Shale	631	