

CORE DESCRIPTION ✓

PAULSEN #7

Cattleman Ss.

<u>Depth</u>	<u>Description</u>
609.0 - 610.0	Ss., fn-med grn., excellent porosity, good saturation
610.0 - 610.1	Gray sticky shale
610.1 - 612.0	Ss. as 609-610
612.0 - 612.8	Shale, dk. gray, sandy, light saturation
612.8 - 613.2	Ibid, barren
613.2 - 615.2	Shale, dk. gray, mica & sandy, lt. stain
615.2 - 615.8	Ss, dk. brn. saturated
615.8 - 616.2	Shale, dk. gray, coal bed (1/8" thick) 45° dip
616.2 - 616.6	Shale, gray
616.6 - 617.2	Ss, med. grn, high porosity, excellent saturation
617.2 - 618.2	Sh, gray
618.2 - 625.0	Ss, med. grn, occ. thin shale lam. (every 2" - 4") excellent saturation, lower one foot heavy saturated with heavy oil and gilsonite occupying fractures
625.0 - 630	Shale, gray

Described by Dwayne McCune