



15-041-20027
31-16-300E

Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

31-16-300E

April 10, 1974

COMPANY: FRANK R. DILTER
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: PIPER #1
 LOCATION: S/2 SW/4, Sec. 31-165-3E,
 Dickinson County, Kansas
 COMMENCED: April 6, 1974
 COMPLETED: April 12, 1974
 ELEVATION:

State Geological Survey
WICHITA, BRANCH

0	to	100	Shale & Linc
100	to	157	Linc
157	to	420	Shale & Linc
420	to	630	Linc & Shale
630	to	1060	Shale
1060	to	1435	Shale & Linc
1435	to	1685	Linc
1685	to	1950	Linc & Shale
1950	to	2105	Linc
2105	to	2260	Linc & Shale
2260	to	2443	Shale
2443	to	2680	Mississippi
2680	to	2781	Shale
2781	to	2905	Linc
2905	to	3000	Shale
3000	to	3100	Linc
3100	to	3130	Linc & Sand
		3130	Y. D.

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1974

CONSERVATION DIVISION
Wichita, Kansas
JAN 1975
RECEIVED
STATE GEOLOGICAL SURVEY OF KANSAS

Cut 12 1/4 inch hole to 157 ft. and run 189.85 ft. of 8 5/8 inch surface pipe, cemented with 125 sacks of cement at 157 ft., plug down at 6:00 p. m., April 6, 1974. Cut 7 7/8 inch hole to 3130 ft., Hole dry and abandoned. Set bottom plug at 170 ft. and cemented with 25 sacks of cement. Set top plug at 40 ft. and cemented with 10 sacks of cement, 2 sacks of cement in rathole. Plugging completed at 11:00 p. m., April 12, 1974. Plugging completed by Hugh Scott, State Plugger, McPherson, Kansas.

TOPS: MISSISSIPPI - 2443'

Measurements taken from K. B.

CERTIFICATE

I, Charles D. Johnson, Secretary - Treasurer, Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Piper #1, located on the S/2 SW/4, Section 31-165-3W, Dickinson County, Kansas as reflected by the files of Blackstone Drilling, Inc.