

Platted 2000
27-16-4E


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - HUTCHINSON OIL & GAS COMPANY
Farm - G. o. Biehler No. 3

SEC. 27 T. 16 R. 4E
SW NW SW

Total Depth. 2371'
Comm. 9-8-47 Comp. 9-15-47 ✓
Shot or Treated.
Contractor. S & H Drilling Company
Issued. 10-18-47

County. Dickinson
KANSAS



Elevation. 1375' act

Production. Dry Hole

CASING:

8-5/8" 139'
5-1/2" 2314' - Pulled

Figures Indicate Bottom of Formations.

yellow clay	30
lime & shale	240
shale	280
lime & shale	715
lime	800
shale	850
lime & shale	1460
lime	1575
lime & shale	1650
sand	1700
lime	1830
lime & shale	1905
lime	2300
shale	2314
chat	2314 Drilled to 2315

Cable Tools

Chat medium hard	2334
green shale	2340
chat medium hard	2342
chat hard	2357
chat soft	2369
green shale	2371
Total Depth	2371

Filled up with 1400' of water
over night and 50' oil.