

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas


27-16-4E

Company - YOUKER & SONS
Farm - Geo. Biehler No. 6

SEC. 27 T. 16 R. 4E
NE SE SW

Total Depth. 2290
Comm. 2-11-50 Comp. 2-19-50
Shot or Treated.
Contractor. Glusser Drlg.
Issued. 4-1-50

County. Dickinson
KANSAS



Elevation. 1367.5nd

CASING:
8" 84'
5" 2240'

Production. Est. 15 bbls oil,
no water

Figures Indicate Bottom of Formations.

soil	15
lime	45
lime, shale	415
shale, shells	580
lime, shale	700
shale	825
lime, shale	1235
lime	1290
lime, shale	1340
lime	1375
lime, shale	1450
lime	1495
lime, shale	1520
shale	1550
sand	1645
shale	1655
lime	2060
lime, shale	2185
shale, shells	2237
chat RFD	2240
Corr: by cable tool ground measurement	
top of chat	2233
chat sft	2236
chat med hrd blue	2251
free oil, very small amount 2251-2260	
chat, lime, hrd wht	2260
chat med hrd	2265
Hole making 1 1/2 bailers oil and water pr hr.	
chat, lime med hrd	2272
chat, lime sft	2281
shale grn	2285
lime hrd	2288
lime 57' in chat	2290
Total depth	

Shooting well:
top of shot 2249
Bottom of shot 2270,
60 qts nitro

200' fluid in hole, 20% wtr
at total depth

Shooting well:
Top of shot 2249'
Bottom of shot 2270', 60 qts. nitro