

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

29-16-4E

Company- ANDERSON-PRICHARD OIL CORP.
Farm- Scully "E" No. 2

SEC. 29 T. 16 R. 4E
SE NW NE

Total Depth. 2321'

Comm. 10-15-55


Comp. 1-22-56

Shot or Treated.

Contractor. Glenn W. Peel

Issued. 2-18-56

County Dickinson
KANSAS



Elevation. 1412' RB

Production. 45 BO & 33 BW 24 hrs.

CASING:

8 5/8" 94' cem.
5 1/2" 2309' cem.

Figures indicate Bottom of Formations.

lime and sand	70
lime and shale	94
lime	270
lime and shale	750
shale and shells	1065
shale and lime	1490
lime	2275
shale and lime	2302
Miss.	2321
Total Depth	

Tops:

Mississippi 2302 Corr. to 2301

R.T.D. 2317 Corr. to 2316

C.T.D. 2321

MICT. Drld cem & show. CO to TD. 3 hrs: bailed
1 1/2 bbls. fluid per hr, 30% oil. DD to 2319.
Swabbed 5 hrs @ rate of 1 3/4 BFPH, est. 30%
wtr. balance muddy oil.
12 hrs: swabbed 9 3/4 BO & 8 1/4 BW.
DD to 2321. 4 hr swab test: 7 BFPH, Est. 6% wtr.
POP.

P/89 BO & 60 BW/22 hrs.

P/45 BO & 24 BW/24 hrs.

P/45 BO & 33 BW/24 hrs.

P/63 BO & 32 BW/24 hrs.

P/52 BO & 27 BW/24 hrs.

5-day average: P/59 BO & 35 BW/24 hrs.