

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


29-16-4E

Company- ANDERSON-PRICHARD OIL CORP.
Ferm- Scully "E" No. 3

SEC. 29 T. 16 R. 4E
NW NW NE

Total Depth. 2317'
Comm. 11-18-55 Comp. 11-24-55
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 2-18-56

County Dickinson
KANSAS



Elevation. 1392' RB

Production. Dry

CASING:

8 5/8" 120' cem.
5 1/2" 2296' cem.

Figures indicate Bottom of Formations.

lime	120	
lime and shale	650	
shale & broken lime	1150	
lime	1335	
lime and shale	1515	
lime	2296	RTD
lime	2317	CTD
Total Depth		

Tops:
Mississippi 2285

Swabbed and bailed casing dry. Drilled cement and shoe at 2296'. DD to 2298'. Bailed 3/4 BWPH w/trace of oil for 2-hrs. DD to 2301'. Bailed 3/4 BWPH w/trace of oil for 4-hrs. DD to 2304'. Bailed 2 BWPH for 4 hrs. w/show of oil. DD to 2306'. Swabbed 3 hrs; .93 BWPH. DD to 2309'. Swabbed 7 1/2 BW/4 hrs. with trace of oil. DD to 2317'. Swabbed 2 BO & 26 BW/6 hrs. Perf. 2291-95. Bailed no fluid. Perf. 2286-91. Bailed 15 gal. water with trace of oil in 16 hrs. Mud acid w/200 gal. Swabbed load and in 2 hrs, 1 1/2 BW, no oil. Bailed 3/4 BWPH for 4 hrs. P & A.