

NCIF 23-16-5E^{PI} and

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Compt. _____

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238. No Log

LICENSE # 6929 EXPIRATION DATE June 30, 1983

OPERATOR Midwestern Oil Producers, Inc. API NO. 15-127-20422

ADDRESS 2030 Fairlawn Rd., Suite #1 COUNTY Morris

Topeka, Kansas 66604 FIELD Grandview

** CONTACT PERSON Les Fetterly PROD. FORMATION Mississippian
PHONE 816-741-3446

PURCHASER Koch LEASE Miller

ADDRESS Box 2256 WELL NO. 1

Wichita, Kansas 67201 WELL LOCATION NW NW NE 23-16-5E

DRILLING Oursler Drilling, Inc. 330 Ft. from N Line and

CONTRACTOR Box 143 2310 Ft. from E Line of (E)

ADDRESS Peabody, Kansas 66866 the NE (Qtr.) SEC 23 TWP 16 RGE 5 (W).

PLUGGING N/A WELL PLAT (Office Use Only)

CONTRACTOR KCC

ADDRESS KGS ☒

TOTAL DEPTH 2300 PBTD 2276 SWD/REP

SPUD DATE 1-8-83 DATE COMPLETED 1-11-83 PLG.

ELEV: GR 1478 DF KB 1484

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 157 DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) Oil Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Sylvester J. Belisle, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

RECEIVED
STATE OF KANSAS
COMMISSION
MAR 14 1983
CONSERVATION DIVISION
Wichita, Kansas

SP-2701-88

ACO-1 WELL HISTORY (E)

OPERATOR Midwestern Oil Producers, Inc. LEASE Miller SEC. 23 TWP. 16 RGE. 5 (W)

FILL IN WELL INFORMATION AS REQUIRED: WELL NO. 1

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
✓ Check if no Drill Stem Tests Run.			Top Cherokee	2192
			Top Mississippian	2222

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used				Depth interval treated	
4000 BBL water, 10,000 # 8-12 Sand				2232-2240	
10,000# 20-40 sand				2250-2254	
20,000# 10-20 sand					
Date of first production		Producing method (flowing, pumping, gas lift, etc.)		Gravity	
March 8, 1983		pumping		33% (est.)	
Estimated Production -I.P.	Oil	Gas	Water	Gas-oil ratio	
	25	bbls.	75 %	bbls.	
Disposition of gas (vented, used on lease or sold)			MCF	CFPB	
			Perforations	2232-2240 2250-2254	

If additional space is needed use Page 2, Side 2

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Secks	Type and percent additives
surface	12½	8 5/8		157	common	150	3% Ca C12
production	7 7/8	4½	9.5	2292.5	60/40 poz	225	5% GIL, 10% Na C1 1% Ca C12

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Secks cement	Shots per ft.	Size & type	Depth interval
		None	1	3½ DML	2232-2240
TUBING RECORD			1	3½ DML	2250-2254
Size	Setting depth	Packer set at			
2 7/8	2220.98 (Gr)	--			