

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


24-16-5E

Company- KOESTER & MERGEN
Farm- Brechbill No. 1

SEC. 24 T. 16 R. 5E
NW NW SW

Total Depth. 2284
Comm. 4-27-53 Comp. 5-20-53
Shot or Treated.
Contractor. Slusser Drilling Co.
Issued. 6-13-53

County Morris
KANSAS



CASING:
8 5/8" 180'
5 1/2" 2229' P.

Elevation. 1482

Production. Dry

Figures Indicate Bottom of Formations.

soil surface	5
lime, shale	180
shale	225
lime, shale	300
lime	360
lime, shale	395
lime	420
shale, shells	930
lime	950
shale, lime	1200
lime, shale	1270
shale, shells	1330
lime, shale	1780
shale	1810
lime	2020
lime, shale	2225
shale	2227
chat	2229 RTD
Cable Tools	
chat soft	2240
chat firm	2247
chat soft	2274
chat & lime	2279
lime, shale	2284
Total Depth	

Tops:
Chat 2227
Kinderhook shale 2281

1st water 2245-2250, scum
oil & 150' wtr overnite.
Good show oil 2258-2265
350' oil & 350' water
overnite.

Drilled deeper., increase
in water; oil decreasing.

Shot 42 Kone shots @ 2258-2265
filled up 75' oil & 650' water
overnite.
Abandoned.