

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY **25-16-5E**
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY KOESTER & MERGEN

SEC. 25 T. 16 R. 5E

FARM Burns

NO. 2

LOC. NE NW SW

TOTAL DEPTH 2237; PB 2227

COMM. 9-3-50

COMP. 9-11-50


SHOT OR TREATED

CONTRACTOR Mendenhall Drilling Co.

ISSUED 12-30-50

COUNTY Morris

KANSAS



CASING

150'

2183'

ELEVATION 1450

PRODUCTION dry

FIGURES INDICATE BOTTOM OF FORMATIONS

oil & clay	22
lime	38
shale & shells	110
shale	115
sand & lime	136
shale & lime	150
lime	210
shale red	213
shale & lime	550
shale & shells	1095
shaley lime	1285
shale & shells	1340
lime	1380
lime & shale	1500
shale & shells	1605
shale & lime	1665
lime	1998
shale	2003
lime	2148
shale & lime	2182
chat, RTD	2213

filling In data:

Drilled plug and shut down
overnite. Fillup 500' water
and scum of oil.

D.D. 2217', no inc. oil.

D.D. 2223½' Inc. Oil.

Fillup 300' oil & 540' water
overnite. Drilled deeper to
2228'. no increase. Placed on
pump. Est. 25 bbls/day
Sept. 24.

Oct. 30th. D.D. 2237' no inc.
oil, possible inc. water.

PB to 2227. Shot 25 qts. Nov.
1st.

Put on pump. Est. 2 to 3 bbls. oil
and much water per day. Abd.

Dec. 8, 1950.

Chat Total Depth 2237

Tops: P. 227

Chat 2182