

26-16-5E

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY KOESTER & MERGEN

SEC. 26 T. 16 R. 5E

FARM Peterson "A" NO. 2

LOC. SW NE SE

TOTAL DEPTH 2292

COMM. 12-11-50

COMP. 1-24-51


COUNTY Morris

SHOT OR TREATED

CONTRACTOR Mendenhall Drlg. Co.

ISSUED 2-24-51

KANSAS



CASING  
8" 165'  
4" 2244'

ELEVATION 1488 Ind.

PRODUCTION dry

FIGURES INDICATE BOTTOM OF FORMATIONS

soil & gravel	15
shale	25
lime	30
shale & lime	148
water	150
lime	162
shale & lime	1015
lime	1025
shale & shells	1140
lime	1175
shale & lime	1420
lime	1435
shale & lime	1480
lime	1490
lime & shale	1735
lime	2045
lime & shale	2115
lime	2180
shale & lime	2236
chat	2239, RTD
chat	2291
shale	2292
Total depth	

Scout Tops:  
 Chat 2236  
 Kinderhook shale 2291

Remarks:  
 D.S. & D.D. 2240' rainbow show heavy oil. D. D. 200' water overnite @ 2248-2256'.  
 Inc. water @ 2267-2274. 800' water overnite. Inc. water @ 2274-2291' 1300' water overnite.  
 No noticeable increase in oil below 2240'.