

State Geological Survey
WICHITA, BRANCH
KANSAS DRILLERS LOG


IMPORTANT
Kans. Geo. Survey request
samples on this well.

API No. 15 — 127 — 20,069
County Number

24 T. 16 R. 7 E
Loc. SW SE SW

County Morris

640 Acres
N



Locate well correctly

Elev.: Gr. 1406

DF KB 1411

Operator

Brandt Oil Company

Address

Suite 140, 9505 West Central, Wichita, Kansas 67212

Well No.

#1

Lease Name

Campbell

Footage Location

405 feet from ~~ND~~ (S) line 1990 feet from ~~ND~~ (W) line

Principal Contractor

Brandt Drilling Co.

Geologist

Earl O. Brandt

Spud Date

Oct. 16, 1975

Total Depth

2910

P.B.T.D.

Date Completed

Oct. 25, 1975

Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2	8 5/8	28	126		65	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)		
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Brandt Oil Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Dry Hole

Well No. # 1
Lease Name Campbell

S 24 T 16 R 7 E
2005

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Lime & chert and cherty lime	0	176	Heebner	1392 ($\pm$ 19)
Lime & shale	176	1075		
Lime chalk	1075	1121	Landing	1646 (-235)
Lime & shale	1121	1367		
Lime	1367	1392	B.Kan.City	2011 (-600)
Shale, black	1392	1396	Cherokee Sh.	2216 (-805)
Lime	1396	1404		
Shale & sandy shale	1404	1415	Miss.Chert	2443 (-1032)
Lime	1415	1645	Miss.Lime	2489 (-1078)
Shale & sandy shale	1645	2011		
Lime	2011	2094	Kinderhook	2565 (-1154)
Shale	2094	2216	Misener Sd.	2736 (-1325)
Shale & Lime & sand streaks	2216	2220		
Chert	2220	2343	Hunton Dolo.	2741 (-1331)
Lime	2343	2389		
Shale, gray ,green	2389	2565	Maquoketa	2822 (-1411)
Sand, hard	2565	2736	Viola	2903 (-1492)
Dolo. hard porous	2736	2741	RTD	2910 (-1499)
Shale gray & green	2741	2822		
Dolo. cherty, show oil	2822	2903		
RTD	2903	2910		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Earl O. Brandt Signature

Owner

Title

October 27, 1975

Date