

20-16-8E

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- WHITE & ELLIS et al  
Farm- Wilson No. 1

SEC. 20 T. 16 R. 8E  
NW NW SW

Total Depth. 3226  
Comm. 5-20-57 Comp. 6-24-57  
Shot or Treated.  
Contractor. White & Ellis Drilling, Inc.  
Issued. 7-27-57

County Morris

KANSAS



Elevation. 1352 RB

CASING:

8 5/8 183' w/ 125 sx cmt.

Production. Dry

Figures indicate Bottom of Formations.

clay	15	lime	2639
shale	30	brown sandy dolomite, no odor	2649
shale & shells	40	lime	2692
red rock	50	shale & lime	2867
lime	110	lime, show no odor	2928
red rock	115	shale	3008
lime	130	lime	3082
shale	145	sand	3179
lime	170	lime	3226
shale	175	Total Depth (KBM 5' above GL)	
lime	264		
shale & shells	290	TOPS: (KBM)	
lime	305	Lansing	1614
shale & shells	340	Kansas City	1736
lime	400	Mississippi	2493
shale & shells	473	Kinderhook	2692
red bed	478	Hunton	2867
shale & shells	534	Maquoketa	2928
red bed	540	Viola	3008
shale & shells	645	Simpson	3082
shale & lime streaks	920	Arbuckle	3179
lime	965		
shale & shells	975		
shale & lime streaks	1046	lime	1765
lime	1070	shale	1785
shale	1090	lime	1970
shale & lime streaks	1110	shale & shells	1992
lime	1125	shale & lime streaks	2015
shale & lime streaks	1180	shale & shells	2075
shale	1220	lime & shale streaks	2088
shale & lime streaks	1233	shale & shells	2105
shale	1340	lime & shale streaks	2111
lime	1355	shale & shells	2172
shale	1415	lime & shale	2198
shale & shells	1522	shale & shells	2216
lime & shale streaks	1579	gray shale & sandy shells	2247
lime	1602	shale & lime streaks	2346
dark shale	1614	lime & shale streaks	2493
lime	1648	Mississippi chat	2509
dark shale	1736		