

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


26-16-8E

Company- E. H. ADAIR OIL COMPANY, ET AL  
Farm- Droll No. 1

SEC. 26 T. 16 R. 8E  
NE NE SW

Total Depth. 3149'  
Comm. 12-21-56 Comp. 12-31-56  
Shot or Treated.  
Contractor. Rex & Morris  
Issued. 1-19-57

County Morris  
KANSAS



Elevation. 1363' KB

Production. Dry

CASING:

8 5/8" @146' w/125 sx cem.

Figures Indicate Bottom of Formations.

shale	1060	Dolomite	3143
lime	1150	sand	3149
shale	1563	Total Depth	
lime	1573	TOPS	
shale	1575	Lansing	1568
lime	1601	Base/Kansas	
shale	1605	City	1938
lime	1615	Burgess	2478
shale	1622	Mississippi	2496
lime	1643	Kinderhook	2731
shale & lime	1692	Hunton	2879
lime	1711	Maquoketa	2958
Oolitic lime	1722	Viola	3026
lime	1727	Simpson sand	3143
Oolitic lime	1741		
lime	1796		
shale	1803		
lime	1820		
shale	1822		
shale & lime	1884		
lime	1892		
shale	1898		
shale & lime	1928		
lime	1938		
shale	2035		
lime	2043		
shale	2068		
lime	2078		
shale & lime	2092		
shale	2117		
lime	2122		
shale	2127		
lime	2138		
shale	2160		
shale & lime	2172		
shale	2177		
lime	2180		
shale	2398		
limey shale	2408		
shale	2478		
sandy shale	2496		
lime	2512		
shale	2514		

DRILL STEM TESTS

DST #1 3027-34 op 1 hr.  
shut-in 20 min. Weak blow  
thr-out test. Rec. 105'  
muddy-wtr. BHP 1040#.

DST #2 Straddle test;  
2880-2900. op. 30 min.  
good blow for 19 min.  
Rec. 2275' salt-wtr.  
IFP 760# FFP 1020#,  
BHP in 20 min. 1040#.

cherty lime	2540
lime	2544
shale	2548
lime	2556
cherty lime	2567
lime	2574
shaley lime	2579
cherty lime	2628
lime	2679
shale	2684
lime	2731
shale	2879
Dolomite	2958
Shaley Dolomite	3026
Dolomite	3063
Cherty Dolomite	3102
shale	3106

