

16-16-9E ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
502 East Murdock, Wichita, Kansas

Company- LEE BANKS, ETAL
Farm- Young No. 1

SEC. 16 T. 16 R. 9E
 C NE NW

Total Depth. 3179
Comm. 11-15-65 Comp. 11-23-65
Shot or Treated.
Contractor. White & Ellis Drlg.
Issued. 1-15-66

County Morris
KANSAS



CASING:

Elevation. 1336' KB

8 5/8" 182' w/135 sx.

Production. Dry

Figures Indicate Bottom of Formations.

lime & shale (stks.)	0-40
lime	74
lime & shale stks.	182
shale & lime stks.	740
shale	790
shale & sand	870
shale & lime	930
lime	970
shale & lime stks.	1239
lime	1270
shale & lime stks.	1540
lime	1584
shale & lime	1683
lime	1915
shale	1965
sand & shale	2004
lime & shale	2140
shale w/lime stks.	2320
shale & lime stks.	2450
shale & sand	2493
lime	2500
shale & cherty Conglomerate	2542
lime	2829
shale	2967
lime	3059
shale	3130
lime	3179
Total Depth	

TOPS: Log

Heebner	1260
Lansing	1536
Cherty Conglomerate	2500
Mississippi	2516
Mississippi (lime)	2542
Mississippi (Cherty)	2660

Kinderhook	2828
Hunton	2967
Hunton	2970
Maquoketa	3060
Viola	3155