

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


9-17-11E

Company- STANOLIND OIL & GAS CO.
Farm- Neil Christensen No. 1

SEC. 9 T. 17 R. 11E
SW SW NW
2310' S of NL, 330' E of WL, NW

Total Depth. 3015
Comm. 3-12-52 Comp. 3-31-52
Shot or Treated.
Contractor.
Issued. 5-24-52

County Lyon KANSAS



CASING:
8 5/8" 217' cem. w/325 sx

Elevation. ~~1267 RDB~~
1265 (m)

Production. Dry

Figures Indicate Bottom of Formations.

clay, shells	45
shale, shells	125
lime, shale, shells	217
shale, shells	300
shaley lime	700
shale, lime brkn	855
shale, shells	1000
shale, lime strks	1236
lime	1316
shale	1350
shale	1375
lime	1396
lime, wtr content	1543
lime	1570
lime, shale	1603
shale	1650
shale, lime	1695
sandy shale	1734
shale, lime	2249
cherty lime	2275
lime	2462
cherty lime	2500
chert	2512
cherty lime	2548
lime	2652
shale	2781
sand, lime	2786
cherty lime	2795
lime, oil specks	2930
sand, lime oil scum	2965
sand	2966
shale	2970
sandy lime	2988
lime, sulphur water	3015
Total Depth	

Tops:	
Lansing	1236
Kansas City	1350
Marmaton	1734
Mississippi	2249
Kinderhook	2652
Hunton	2781
Viola	2795
Simpson	2930
Arbuckle	2988

Sands:	
Simpson	2930-2988
Arbuckle	2988-3015