

500 East Main St
Wichita, Kansas


13-17-11E
SW SW NE

AUG 28 1971

CASING RECORD

8 5/8" 177' Cemented
w/115 sacks

Location: SW SW NE
Section: 13-17S-11E
Lyon County, Kansas
Farm: Sellers #1



Well Owner: Aladdin Petroleum Corp.
Contractor: WHITE & ELLIS DRILLING, INC.
Commenced: 6-29-71
Completed: 7-9-71

Total Depth 2964'

KELLY BUSHING MEASUREMENT 5' ABOVE GROUND LEVEL ELEVATION: 1250'KB

FORMATION	DEPTH
Shale & Lime (Stks.)	0-1141
Lime	1280
Shale	1282
Lime	1537
Shale	1670
Shale & Lime (Stks.)	1950
Shale	1995
Core #1	2040
Shale	2160
Lime	2598
Shale	2732
Lime	2868
Sand	2927
Lime	2964

DRY/ARB

LOG TOPS:

Iatan	1141
Lansing	1163
Kansas City	1282
B " "	1530
Marmaton	1644
Cher.	1770
Bart Sd	1991
Mississippi	2194
Kinderhook	2600

Mz PLUGGED & ABANDONED

Hunton	2732
Viola	2773
Simpson Dol	2844
" Sd	2877
Arbuckle	2927

TOPS

Lansing	1141
Kansas City	1282
Mississippi	2160
Hunton	2732
Viola	2773
Simpson	2868
Arbuckle	2958

DST (1) 2874-77
DST (2) 2879-82