



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

May 18, 1978

Glenn Evans
Rural Route 1
Zimmerman, Minnesota 55398

Dear Mr. Evans:

Enclosed herewith are the results of tests run on the rotary core taken from the Evans Lease, Well No. 5-A, Franklin County, Kansas, and submitted to our laboratory on May 16, 1978.

The core was sampled by a representative of the client.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Benjamin R. Pearman
Benjamin R. Pearman

BRP:vm
5 c to Zimmerman, Minnesota

OILFIELD RESEARCH LABORATORIES

- LOG -

Company Glenn Evans Lease Evans Well No. 5-A

<u>Depth Interval, Feet</u>	<u>Description</u>
751.0 - 752.0	Brown slightly shaly sandstone.
752.0 - 752.6	Brown and gray laminated shaly sandstone.
752.6 - 757.0	Brown sandstone.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1-B

Company Glenn Evans Lease Evans Well No. 5-A

Sample No.	Depth, Feet	Effective Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.	Feet of Sand		Total Oil Content	Perm. Capacity Ft. X md.
			Oil	Water	Total			Ft.	Cum. Ft.		
1	751.5	18.6	56	37	93	810	47.	1.0	1.0	810	47.00
2	752.5	15.2	33	60	93	390	9.7	0.6	1.6	234	5.82
3	753.5	23.1	53	29	82	952	113.	1.4	3.0	1,333	158.20
4	754.5	23.4	46	31	77	837	296.	1.0	4.0	837	296.00
5	755.5	23.0	33	27	60	590	130.	1.0	5.0	590	130.00
6	756.5	19.7	44	28	72	674	72.	1.0	6.0	674	72.00