

OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

August 24, 1982

Triple-I Energy Corporation
8100 Marty, Suite 117
Overland Park, Kansas 66204

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Caylor Lease, Well No. 34, located in Section 33, T-17S, T-21E, in Franklin County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and was submitted to our laboratory on August 20, 1982.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES



Sanford A. Michel

SAM/rmc

4 c to Overland Park, Kansas
1 c to Hutchinson, Kansas

OILFIELD RESEARCH LABORATORIES

LOG

Company Triple-I Energy Corporation Lease Caylor Well No. 34

<u>Depth Interval, Feet</u>	<u>Description</u>
755.0 - 756.0	Grayish brown slightly shaly sandstone.
756.0 - 757.0	Brown sandstone.
757.0 - 759.0	Grayish brown shaly sandstone.
759.0 - 762.0	Gray shale.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Triple-I Energy Corp. Lease Caylor Well No. 34

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	755.7	19.6	38	31	69	578	7.8
2	756.6	18.9	45	26	71	660	14.
3	757.5	20.2	53	21	74	831	2.1
4	758.5	21.8	46	20	66	778	5.5