



# OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

May 11, 1981

Oaks Petroleum, Inc.  
c/o Calvin T. Oaks, Jr.  
R R # 2  
Stoystown, Pennsylvania 15563

Gentlemen:

Attached hereto are the results of tests run on the rotary cores taken from the Peckham Lease, Well No. P-3, located in Franklin County, Kansas.

The cores were sampled and sealed in plastic bags by a representative of the client and were submitted to our laboratory on May 4, 1981.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/kas

T175, R21E, Sec 9

2 c to Stoystown, PA  
3 c to Paola, KS

## OILFIELD RESEARCH LABORATORIES

LOGName Oaks Petroleum, Inc. Lease Peckham Well No. P-3

<u>Depth Interval, Feet</u>	<u>Description</u>
	<u>2nd &amp; 3rd SQUIRREL SANDS</u>
	<u>2nd SQUIRREL SAND</u>
563.0 - 567.0	Grayish light brown slightly calcareous shaly sandstone.
	<u>3rd SQUIRREL SAND</u>
574.0 - 575.7	Gray and light brown laminated slightly calcareous shale and sandstone.

# Oilfield Research Laboratories

## RESULTS OF SATURATION & PERMEABILITY TESTS

### TABLE 1

Company Oaks Petroleum, Inc. Lease Peckham Well No. P-3  
2nd Squirrel Sand

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	563.4	19.8	55	19	74	845	Imp.
2	564.5	20.4	32	36	68	506	Imp.
3	565.5	15.5	44	51	95	529	Imp.
4	566.4	20.0	25	43	68	388	Imp.