



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

July 12, 1982

Bob Kleier
R. R. # 1
Wellsville, Kansas 66092

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Eneihen Lease, Well No. 6, located 585' from the South Line and 265' West of the East Line, of the Southeast $\frac{1}{4}$, in Section 4, T-17S, R-21E, in Franklin County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and was submitted to our laboratory on July 9, 1982.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/dlb

5 c to Wellsville, Kansas

- REGISTERED ENGINEERS -

CORE ANALYSIS - WATER ANALYSIS - REPRESSURING ENGINEERING - SURVEYING & MAPPING - PROPERTY EVALUATION & OPERATION

OILFIELD RESEARCH LABORATORIESLOGName Bob Kleier Lease Eneihen Well No. 6Depth Interval,
FeetDescriptionSECOND SQUIRREL SAND

532.0 - 533.5

Grayish brown shaly sandstone.

533.5 - 537.0

Grayish brown very shaly sandstone.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE I

Company Bob Kleier Lease Eneihen Well No. 6

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbla. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	532.6	22.4	22	42	64	382	2.7
2	533.4	21.5	10	51	61	167	5.8
3	534.4	15.7	13	77	90	158	0.17
4	535.3	16.0	18	74	92	223	Imp.
5	536.3	14.9	10	83	93	116	Imp.