



# OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

October 21, 1982

Bob Kleier  
R. R. # 1  
Wellsville, Kansas 66092

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Eneihen Lease, Well No. 10, located in Section 4, T-17S, R-21E, Franklin County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and submitted to our laboratory on October 19, 1982.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/rmc

5 c to Wellsville, Kansas

**OILFIELD RESEARCH LABORATORIES**

LOG

Company Bob Kleier Lease Eneihen Well No. 10

Depth Interval,      Description  
Feet                    \_\_\_\_\_

SECOND SQUIRREL SANDSTONE

646.0 - 648.0      Brown slightly calcareous sandstone.

648.0 - 652.0      Grayish brown very shaly sandstone.

# **Oilfield Research Laboratories**

## **RESULTS OF SATURATION & PERMEABILITY TESTS**

**TABLE 1**

Company Bob Kleier Lease Eneihen Well No. 10

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A. Ft.	Permeability, Millidarcys
			Oil	Water	Total		
1	646.5	21.2	58	13	71	954	47.
2	647.5	20.4	34	38	72	538	21.
3	648.5	14.5	35	60	95	394	Imp.
4	649.4	15.4	28	63	91	335	0.31
5	650.4	14.6	23	74	97	261	0.63
6	651.4	15.4	44	50	94	526	Imp.