



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

August 29, 1980

A & S Oil & Gas, Inc.
c/o Don Bogle
R R # 5, Space 23
Paola, Kansas 66071

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Meinig Lease, Well No. 2, located in the SW $\frac{1}{4}$ of the SW $\frac{1}{4}$ in Section 22, T-17S, R-22E, Miami County, Kansas and submitted to our laboratory on August 22, 1980. Sect. 15?

The core was sampled and sealed in plastic bags by a representative of the client.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES


Sanford A. Michel

SAM/ks

5 c to Paola, Kansas

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company A & S Oil & Gas, Inc. Lease Meinig Well No. 2

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	503.5	15.3	45	43	88	534	2.7
2	504.5	16.3	34	53	87	430	2.1
3	505.5	14.5	36	50	86	405	2.4
4	506.3	15.0	30	55	85	349	2.9
5	507.5	15.6	38	56	94	460	11.
6	508.5	18.0	32	54	86	447	9.9