

Sec. 12, T. 17 S., R. 23 E.  
SW SE NW

Year Well Reported \_\_\_\_\_

API Serial Number 15 - -

KANSAS WELL COMPLETION REPORT 12-17-23E

INSTRUCTIONS: Within 30 days after completion of this well the owner or operator should complete the form and mail it to Margaret Oros, Chairman, AAPG-CSD District 12, State Geological Survey of Kansas, Lindley Hall, Lawrence, Kansas 66044, in the enclosed stamped, self-addressed envelope. (The information given in the IBM print-out is taken from the "Intents-to-Drill" list of the Oil and Gas Conservation Division of the State Corporation Commission of Kansas, 500 Insurance Building, Wichita, Kansas 77602. Please correct any item that is in error.)


Miami Co.

Stephen Young #1 Steven Russell

\*\*\*\*\*

Date Drilling Began: 11/9/68

Please show  
location of  
well in  
section:



Date Drilling Completed: 11/14/68

Hole completed as (check): Dry X ;

Oil   ; Gas   ; Service well   

Elevation: Derrick floor not known

Total depth of hole: 308

Kelly Bushing    Ground   

Name of

formation at total depth:     
(Pleasanton Shale)

Electric or other  
logs were run: Yes    No X

If OWWO\*, give new  
footage drilled:   

Well was Cored: Yes    No X

Field Name: Paola-Rantoul

Drill Stem Test Run: Yes    No X

Name of Company purchasing oil or gas:   

\*\*\*\*\*

Initial Potential or Production:   

Barrels of oil/day    ;

Barrels of water/day    ;

Thousand cu ft gas/day   

Oil Gravity    °API;

Pay Depth (Bottom)   

Net Pay Thickness    Ft.;

Name of Pay Zone   

Please use other side of sheet for additional information. Copy of  
driller's log, electric logs, and other well information would be  
appreciated. (\* OWWO - Old hole re-worked or deepened.)

The AAPG's Committee on Statistics of Drilling (CSD) on January 1, 1966 began compiling data on wells reported drilled in the U. S., Canada, and Mexico. The Oil and Gas Journal has contracted to publish weekly statistical summaries of the data. These will be used by the International Oil Scouts Assoc., American Petroleum Inst., U. S. Bureau of Mines, and other groups, and will be considered the official source of drilling information by the U. S. Department of the Interior.

Many of the wells drilled in southeastern Kansas are not presently scouted. Because of this the CSD District 12 Chairman is sending this Well Completion Report form to all operators who have stated their intent to drill a well. The information received will also be placed on open file in the Oil and Gas Division offices of the State Geological Survey of Kansas. The cooperation of all of the operators in returning the completed form will be greatly appreciated.

(over)

L

12-17-23 E

Stephen Young, #1 Rur well  
Sec. 12 - T. 17 S. - R. 23 E., Miami County,  
SW SE NW

Drillers Log.

16 Ft.,	Soil & Gravel	16 Ft.	Zola
10	, Lime	26	
16	, Shale	42	
29	, Lime	71	
6	, Shale	77	
20	, Lime	99	
3	, Lime	102	
5	, Shale	107	Fresh water )possibly up to
4	, Lime )	111	50 gal per min
4	, Sandy Lime) Hertha	115	Fresh water)
35	, Dark shale	140	
7	, Sandy shale	147	Knob Town Section, Oil Show
88	, Dark Shale	235	
60	, Light Shale	295	
2	, Lime & Shale	297	
5	, Light Shale	302	
5	, Dark Shale	308	

16 feet  $8\frac{1}{4}$  pipe

263 " 7 pipe

Pipe pulled and well plugged 11/15/68.

State Plugger Jim McDaniels, Wellsville, Kansas.

Cement plug from 125 ft. to 155 ft.  
Completed as fresh water well.

11/14/68