

file

✓

TRIAN B9

Core Description
Cattleman Ss.

690 - 690.7	Ss; fn. grn, excellent porosity & saturation. pyrit.
690.7- 691.6	Shale; gray w/few thin saturated Ss. lam.
691.6- 693.7	Ss; fn. grn, excellent quality
693.7- 696.5	Shale; gray, mica, barren
696.5- 703	Ss; excellent porosity & perm., excellent saturation, fn. med. grn., mica. 30° bdg. plane
703 - 710.5	Ss; as above but very tight
710.5- 711	Ss; black, friable, strong odor, tarry
711 - 713	Ss; as above

23 feet total
- 3.7 feet shale
19.3 feet oil sand
- 2.5 feet tar sand

16.8 feet net sand