

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock,  
 Wichita, Kansas


28-17-4E

Company- FRANCIS R. LORIAUX  
 Farm- B.F. Bevans "D" No. 6

SEC. 28 T. 17 R. 4E  
 C E $\frac{1}{2}$  NE $\frac{1}{4}$

Total Depth. 2460' PB 2436'  
 Comm. 10-26-58 Comp. 11-10-58  
 Shot or Treated.  
 Contractor. Slusser Drlg. Co.  
 Issued. 1-17-59

County Marion  
 KANSAS



Elevation. 1501' RB

Production. 20 BOPD

CASING:

8 5/8" 140' w/80 sx cem.  
 4 1/2" 2412' w/40 sx cem.

Figures indicate Bottom of Formations.

surface soil	5
shale	90
shale, lime	645
shale, shells	1025
shale, lime	1485
shale	1590
shale, lime	1840
lime	2015
lime, shale	2120
lime	2170
shale, lime	2406
chat	2412 RTD

CABLE TOOL:

2412-2420	chat very slight show oil
2420-2436	chat Firm
2436-2441	chat soft
2441-2446	shale
2446-2458	chat, shale
2458-2460	shale
Total Depth	
PB	2436

TOPS: SCOUT  
 Mississippi 2405

TREATMENT RECORD: 11-9-58 Dowell  
 Inc. fractured well w/1635 BW and  
 20,000# sand (15,00# of 20/40 and  
 5,000# of 10/200 behind 100 gal.  
 BDS acid. Breakdown pressure from  
 1200psi.-Treating pressure Max.  
 1400 psi. to 1200 psi. Vinal Vacuum.  
 Ave. Pump rate 37 BPM, Total fluid  
 1647 BBLs. Total pump time 44 min.