

OP

REX AND MORRIS ET AL.
Rudolph No. 1.

SEC. 36 T. 17 R. 3E.
NE 3E

Total Depth. 2475'
Comm. 7-26-40 Comp. 9-8-40
Shot or Treated.
Contractor, Rex and Morris Drilg. Co.
Issued. 9-28-40

County Marion.



CASINO.

12 1/2" 93' All pulled.
10" 1440' UR 1494' All pulled.
8 1/4" 1672' UR 1844' All pulled.
7" 2417' All Pulled.

Elevation. 1455

Production. DRY.

Figures Indicate Bottom of Formations.

collar	8	lime broken	845	shale	1805
clay yellow	40	shale white	850	lime	1820
mud yellow	65	hole caving 850		shale	1855
shale blue.	70	shale	900	lime	1860
sand	80	lime	910	shale	1865
HFV 70-80		shale	925	lime	1895
shale white	90	lime	930	shale	1900
shale pink	93	shale	970	lime	1945
shale	100	lime	980	hole caving.	
lime	120	shale	1060	shale	1950
shale	140	lime	1075	lime	2020
red rock	150	shale	1080	shale	2045
shale	170	lime	1085	lime	2145
lime	180	shale	1105	1 BWPH 2095-2100	
shale	185	shale and shells	1115	shale	2155
lime	190	lime	1125	lime	2210
shale	205	shale and shells	1140	hole caving. 2175-2200	
red rock	215	shale	1265	shale & shells	2225
lime	240	lime	1275	lime	2240
lime broken	265	shale	1320	shale Var. colored	2250
shale	270	lime broken	1335	Various colored shale	
lime broken	335	lime	1360	and lime shells	2260
lime	350	shale	1365	shale	2280
shale	360	lime	1385	lime	2285
red rock	370	shale	1415	shale and shells	2340
lime	380	lime	1440	lime	2350
shale	395	shale	1450	shale and shells	2375
lime	410	lime	1455	shale	2414
shale	425	shale	1470	chat	2457
lime	430	lime	1480	1 BWPH 2430	
shale	445	sand	1490	4 BWPH 2435	
lime	455	shale	1510	HFV 2450-2457	
shale	465	lime	1520	lime wh soft	2475
red rock	470	shale	1530	hole filled with	
shale	505	lime	1565	water 1500' in 2 hours	
lime	515	shale	1575	between 2457-2465'	
shale	545	lime	1635	total water in hole 2000'	
shale and shells	580	shale	1640		
1 BWPH 545-50		lime broken	1680		
lime	590	5 BWPH 1660-1670		Total Depth	2475
shale	605	5 BWPH 1670-1680		Plugged and abandoned.	
red rock	625	total 10 BWPH.			
lime broken	635	hole caving 1680'			
lime	645	lime	1685		
shale and lime	680	shale	1710		
shale & shells	720	sand	1740		
lime	745	lime hard	1745		
shale	765	sand	1760		
shale and shells	780	shale sdy	1765		
shale	825	lime	1775		
lime	830	sand	1790		
sand	835	lime hard	1790		
7 BWPH 830-835		lime	1800		

HFV Chat
D.S. 998