



Blackstone Drilling, Inc.

523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

October 19, 1977

State Geological Survey

WICHITA, BRANCH

AUG 8 0 RECD

30-18-1E

COMPANY: CAL JONES

CONTRACTOR: BLACKSTONE DRILLING, INC.
"B"

FARM: G & C #2

LOCATION: SW/4 NE/4 SW/4 Section 30-18-1E,
Marion County, Kansas

COMMENCED: October 12, 1977

COMPLETED: October 18, 1977

ELEVATION:

0	to	95	Sand & Shale
95	to	131	Blue Shale
131	to	530	Shale & Lime
530	to	980	Lime & Shale
980	to	1890	Shale & Lime
1890	to	2086	Lime
2086	to	2355	Lime & Shale
2355	to	2685	Lime
2685	to	2775	Lime & Shale
2775	to	2869	Shale & Lime
		2869	T. D.

Cut 12 1/4" hole to 131' and run 133' of 8 5/8" surface pipe, cemented with 100 sacks of cement at 131'. Plug down at 1:45 P. M., October 13, 1977. Cut 7 7/8" hole to 2869'. Run 2861.84' of 5 1/2" casing, cemented 2' off bottom at 2867' with 40 sacks of cement. Plug down at 9:45 P. M., October 18, 1977.

TOPS: LAWSING - 2265' MISSISSIPPI - 2849'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your G & C #2, located SW/4 NE/4 SW/4 Section 30-18-1E, Marion County, Kansas as reflected by the files of Blackstone Drilling, Inc.


P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 19th day of October, 1977.


Johnnie L. Schmidt - Notary Public

