



AUG 8 0 RECD

Blackstone Drilling, Inc.

Box ¹¹⁸⁴ 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

June 13, 1978

30-18-1E

COMPANY: CAL JONES
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: G & C FARMS "B" #3 ✓
 LOCATION: NE SW SE Section 30-18-1E,
 Marion County, Kansas
 COMMENCED: June 3, 1978
 COMPLETED: June 9, 1978
 ELEVATION:

0	to	25	Clay
25	to	90	Sands
90	to	136	Blue Shale
136	to	885	Lime & Shale
885	to	1670	Shale
1670	to	1943	Shale & Lime
1943	to	2274	Lime
2274	to	2315	Lansing
2315	to	2485	Shale & Lime
2485	to	2856	Lime
2856	to	2883	Mississippi
		2883	T. D.

Cut 12 1/2" hole to 136' and run 138' of 8 5/8" surface pipe, cemented with 100 sacks of cement at 136'. Plug down at 12:00 Noon, June 3, 1978. Cut 7 7/8" hole to 2883'. Run 2886' of 5 1/2" pipe, cemented at 2880', 3 feet off bottom with 50 sacks of cement. Plug down at 8:15 A. M., June 9, 1978.

TOPS: LANSING - 2274' MISSISSIPPI - 2856'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is true and correct copy of log on your G & C Farms #B-3, located on the NE/4 SW/4 SE/4 Section 30-18-1E, Marion County, Kansas as reflected by the files of Blackstone Drilling, Inc.

P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 14th day of June, 1978.

Johnnie L. Schmidt - Notary Public

