



## Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250  
McPHERSON, KANSAS 67460

June 7, 1979

State Geological Survey  
WICHITA, KANSAS  
AUG 8 0 REC'D.

30-18-1E

AUG 8 0 REC'D.

COMPANY:	CAL JONES
CONTRACTOR:	BLACKSTONE DRILLING, INC.
FARM:	G & C FARMS #3
LOCATION:	2310' WEL & 330' NSL SE/4 Section 30-18S-1E, Marion County, Kansas
COMMENCED:	May 30, 1979
COMPLETED:	June 6, 1979
ELEVATION:	

0	to	25	Clayt
2	to	100	Sand
100	to	489	Shale
489	to	800	Shale & Lime
800	to	1050	Shale
1050	to	1750	Shale & Lime
1750	to	2060	Lime & Shale
2060	to	2385	Shale & Lime
2385	to	2578	Lime
2578	to	2703	Lime & Shale
2703	to	2785	Shale & Lime
2785	to	2809	Lime & Shale
2809	to	2845	Cherokee
2845	to	2870	Mississippi
		2870	T. D.

Cut 12 $\frac{1}{4}$ " hole to 126' and run 128' of 8 5/8" surface pipe, cemented with 100 sacks of cement at 126'. Plug down at 9:00 A. M., May 30, 1979. Cut 7 7/8" hole to 2870'. Run 2879' of 5 $\frac{1}{2}$ " casing, cemented at 2870'. Plug down at 12:15 P. M., June 5, 1979.

TOPS:      CHEROKEE - 2805'      MISSISSIPPI - 2845'

Measurements taken from K. B.

### CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your G & C Farms #3, located on the 2310' WEL & 330' NSL SE/4 Section 30-18S-1E, Marion County, Kansas as reflected by the files of Blackstone Drilling, Inc.

  
P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 22 day of June, 1979.

  
Johnnie L. Schmidt - Notary Public

